BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division

SCHEDULE-II

NAME OF THE WORK: **Providing Fencing, Grill Work & other work to Indira Canteen in Ward No.14,Bagalagunte**

Sl. No	Description of work	Unit	Qty	Sanctioned Estimate Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)	Mtr	105.00	860.00	Rupees Eight Hundred Sixty Only
2	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (	Sqm	200.00	690.00	Rupees Six Hundred Ninety Only
3	Fabricating, providing and erecting in Position of Security Grill Work. The entire frame work is tobe fixed by means of expansion bolts to the brick pillars with necesarydrillling holes. the work includes providng two coats of enamel painting over one coatr of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using hoist pulleycranes with alllead and lift, loading, transporting and unloading using hoist pulley cranes, scaffolding charges and all other incidental charges required for successful completion fo the work as per specification and drawings as per direction of Engineer-in-charge of the work	Sqm	25.00	9650.00	Rupees Nine Thousand Six Hundred Fifty Only

S. Manjunath.
Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

roviding and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. with primer	Sqm	172.00	90.00	Rupees Ninety Only
Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	280.00	30.00	Rupees Thirty Only

S. Manjunath
nature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner